

## WIND LOADING CRITERIA

3-SECOND GUST WIND SPEEDS AT 33 FT ABOVE GRADE (MPH) BASED ON DESIRED RISK CATEGORY TOPOGRAPHIC CATEGORY 1, EXPOSURE CATEGORY C,  $Z_s = 0$  FT. ANSI/TIA-222-H

ULTIMATE WIND SPEED ASCE 7-16	85	90	95	100	105	110	115	120	130	140	150
MAX EPA (SQ FT)	250	250	250	246	217	190	165	140	80	29	N/A

(12) 7/8 INCH LINES ON A WAVEGUIDE LADDER, (1) 3/8 INCH SAFETY CABLE MAXIMUM APPURTENANCE WEIGHT: 3,000 LBS WITHOUT ICE AND 6,000 LBS WITH ICE TABULATED EPA VALUES INCREASED 100% FOR ICE LOADING CONDITION TABULATED EPA VALUES LIMITED TO A MAXIMUM OF 250 SQ FT k<sub>2</sub>=1.0 FOR ALL TABULATED EPA

	LOADING RITERIA	EARTHQUAKE LOADING CRITERIA				
MAXIMUM RADI CONCURRENT WI' WIND SPEEI TOPOGRA EXPOSI AN	$\begin{split} S_S &= \text{SPECTRAL RESPONSE ACCELERATION} \\ & \text{PARAMETER AT SHORT PERIODS} \\ S_1 &= \text{SPECTRAL RESPONSE ACCELERATION} \\ & \text{PARAMETER AT 1 SECOND PERIOD} \\ T_L &= \text{LONG PERIOD TRANSITION PERIOD} \\ & \text{SITE CLASS D} \\ & \text{ANSI/TIA-222-H} \end{split}$					
RISK CATEGORY	RISK CATEGORY  ASCE 7-16 500-YR MRI		MAX S <sub>S</sub>	MAX S <sub>1</sub>	T <sub>L</sub>	
I	N/A*	I	N/A*	N/A*	N/A*	
II	2.00	II	2.50	1.00	6.00	
III	1.73	III	2.00	0.80	6.00	
IV	1.63	IV	1.67	0.67	6.00	

\*ICE AND EARTHQUAKE LOADING NEED NOT BE CONSIDERED FOR RISK CATEGORY I STRUCTURES.

## MAXIMUM FACTORED **REACTIONS** TOTAL O.T.M. (FT-KIPS) 3826.07 TOTAL SHEAR (KIPS) 42.24 TOTAL VERTICAL MAX. (KIPS) 88.39 TOTAL VERTICAL MIN. (KIPS) 20.33 MAX COMPRESSION/LEG (KIPS) 219.9 MAX TENSION/LEG (KIPS) 185.34 MAX SHEAR/LEG (KIPS) 24.73

## **GENERAL NOTES**

- 1. THE SUITABILITY OF THE TABULATED TOWER DESIGN CRITERIA FOR A SPECIFIC APPLICATION MUST BE VERIFIED PRIOR TO INSTALLATION BY THE PURCHASER BASED ON SITE-SPECIFIC DATA AND THE INTENDED USE OF THE STRUCTURE.
- 2. ALL USERS ARE SOLELY RESPONSIBLE FOR THE INSTALLATION, USE, MAINTENANCE, INSPECTION, CONDITION ASSESSMENTS AND OTHER WORK TO BE PERFORMED IN COMPLIANCE WITH ALL APPLICABLE INDUSTRY, LOCAL, STATE AND FEDERAL REQUIREMENTS.
- 3. THE TABULATED ALLOWABLE EFFECTIVE PROJECTED AREAS (EPA) REPRESENT THE SUMMATION OF THE PROJECTED AREAS OF ALL ANTENNAS, MOUNTS, AND APPURTENANCES MULTIPLIED BY APPROPRIATE DRAG FACTORS. THE ALLOWABLE PROJECTED AREAS ARE ASSUMED TO BE PLACED SYMMETRICALLY ON THE STRUCTURE. LOWER EPA VALUES MAY APPLY FOR OTHER EPA
- 4. THE FOLLOWING MATERIAL SPECIFICATIONS APPLY TO THE TOWER DESIGN: STRUCTURAL STEEL: 50 KSI MINIMUM YIELD STRENGTH FASTENERS: 120 KSI MINIMUM TENSILE STRENGTH ANCHOR RODS: 125 KSI MINIMUM TENSILE STRENGTH

GALVANIZING: PER ANSI/TIA-222-H

- 5. TOWER FABRICATION SHALL BE BY ROHN PRODUCTS, LLC, CERTIFIED AISC FABRICATOR.
- 6. THE TOWER DESIGN ASSUMES INSTALLATION ON A PROPERLY DRAINED LEVEL SITE. THE TOWER DESIGN MAY REQUIRE MODIFICATIONS FOR INSTALLATIONS ON SITES WITH A SLOPING GRADE OR FOR TOWERS SUPPORTED ON OTHER STRUCTURES.
- 7. INSTALLATION SHALL BE IN ACCORDANCE WITH ANSI/TIA-222-H. INITIAL CONSTRUCTION INSPECTION REQUIREMENTS SHALL BE DETERMINED AND PERFORMED BY THE PURCHASER BASED ON THE LOCATION AND USE OF THE STRUCTURE.
- 8. SAFETY, STRENGTH AND STABILITY REQUIREMENTS FOR THE STRUCTURE FOR CONSTRUCTION AND MAINTENANCE ACTIVITIES SHALL BE IN ACCORDANCE WITH ANSI/ASSE A10.48, "CRITERIA FOR SAFETY PRACTICES WITH THE CONSTRUCTION, DEMOLITION, MODIFICATION AND MAINTENANCE OF COMMUNICATION STRUCTURES" AND ALL APPLICABLE INDUSTRY, LOCAL STATE AND FEDERAL REGULATIONS AND STANDARDS.
- 9. ALL RIGGING, SAFETY EQUIPMENT AND TEMPORARY SUPPORTS REQUIRED FOR CONSTRUCTION AND MAINTENANCE SHALL BE DETERMINED, FURNISHED AND INSTALLED BY THE CONTRACTOR BASED ON THE MEANS AND METHODS CHOSEN BY THE CONTRACTOR. ALL CONSTRUCTION AND MAINTENANCE ACTIVITIES SHALL BE PERFORMED BY COMPETENT, QUALIFIED AND TRAINED PERSONNEL.
- 10. FIELD CONNECTIONS SHALL BE BOLTED. NO FIELD WELDING SHALL BE ALLOWED.
- 11. UNLESS OTHERWISE SPECIFIED, BOLTS SHALL BE TIGHTENED TO A "SNUG TIGHT" CONDITION WITH A NUT-LOCKING DEVICE IN ACCORDANCE WITH ANSI/TIA-222-H WITH NO MINIMUM INSTALLED BOLT TENSION OR TORQUE VALUES REQUIRED.
- 12. STEP BOLTS SHALL BE INSTALLED AS A CLIMBING FACILITY IN ACCORDANCE WITH ANSI/TIA-222-H FOR CLIMBING THE ENTIRE HEIGHT OF THE STRUCTURE. CLIMBING SHALL BE RESTRICTED TO COMPETENT CLIMBERS ONLY.
- 13. A SAFETY CLIMB SYSTEM SHALL BE USED IN ACCORDANCE WITH ANSI/TIA-222-H. ALL CLIMBING FACILITIES, INCLUDING SAFETY CLIMB SYSTEMS, SHALL BE INSPECTED PRIOR TO
- 14. PURCHASER SHALL VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH ALL APPLICABLE INDUSTRY, LOCAL, STATE, AND FEDERAL REQUIREMENTS FOR GROUNDING AND OBSTRUCTION MARKING.
- 15. MAINTENANCE AND CONDITION ASSESSMENTS SHALL BE PERFORMED OVER THE LIFE OF THE STRUCTURE IN ACCORDANCE WITH ANSI/TIA-222-H.
- 16. FOUNDATIONS SHALL BE DESIGNED TO SUPPORT THE TABULATED FACTORED REACTIONS FOR THE CONDITIONS EXISTING AT THE SITE.
- 17. THE PROPER DEVELOPMENT OF ANCHOR RODS FOR THE TOWER SHALL BE VERIFIED BY THE FOUNDATION ENGINEER.

SECTION MAIN MEMBER SCHEDULE						
SECTION	LEGS	DIAGONALS	NOMINAL WEIGHT (LBS)			
RLS04	HSS 2.875 X 0.203	L1 3/4 X 1 3/4 X 1/8	410			
RLS04	HSS 2.875 X 0.203	L1 3/4 X 1 3/4 X 1/8	810			
RLT06	HSS 2.875 X 0.276	L1 3/4 X 1 3/4 X 1/8	1000			
RLT08	HSS 3.500 X 0.300	L1 3/4 X 1 3/4 X 1/8	1290			
RLT10	HSS 3.500 X 0.300	L1 3/4 X 1 3/4 X 1/8	1370			
RLT12	HSS 4.000 X 0.318	L2 1/2 X 2 1/2 X 3/16	2070			
RLT14	HSS 4.500 X 0.337	L2 1/2 X 2 1/2 X 3/16	2410			
RLT16	HSS 4.500 X 0.337	L3 X 3 X 3/16	2830			
RLT18	HSS 5.563 X 0.375	L3 1/2 X 3 1/2 X 1/4	3670			
RLT20	HSS 5.563 X 0.375	L3 1/2 X 3 1/2 X 1/4	3840			

FILE NO. **RTL-CATALOG** DESCRIPTION PO BOX 5999

DWN CHK APP



PEORIA, IL 61601-5999 TOLL FREE 800-727-ROHN

THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED, COPIED OR TRACED IN WHOLE OR IN PART WITHOUT

P/N: RTL190H 190 FT HEAVY SERIES STANDARD RTL TOWER DESIGN ANSI/TIA-222-H

DWN: CEJ	CHK'D:		DATE: 03/24/2022	
ENG'R:	NG	SHEET #: /G 1 OF 1		
PRJ. ENG'R:		PRJ. MAI	NG'R:	
DRAWING NO:			REV/·	

RTL190H-D