Telescoping Mast Guy Kits

NOW AVAILABLE

ROHN Products now offers R-618, 6 strand 18 gauge galvanized wire. R-618 guy wire is shipped in cartons of 1,000'. Each carton is made up of twenty 50' interconnected coils.

ROHN's new R-GAS4303, 3' x 1/2" Screw Anchors offer a low-cost anchor option.

Use R-61820GRPL Gripples for easy installation.

ROHN™ Products LLC

3-Way Guy Kits

R-H203WAYGUY — H20
Actual Wire Required - 200′

1	R-618	1000′ - 6 Strand/18 GA Wire
3	R-GAS4303	3′ x 1/2″ Screw Anchor
12	R-61820GRPL	618/620 Gripple

R-H303WAYGUY — H30
Actual Wire Required - 400′

1	R-618	1000′ - 6 Strand/18 GA Wire
3	R-GAS4303	3′ x 1/2″ Screw Anchor
18	R-61820GRPL	618/620 Gripple

R-H403WAYGUY — H40
Actual Wire Required - 650′

1	R-618	1000′ - 6 Strand/18 GA Wire
3	R-GAS4303	3′ x 1/2″ Screw Anchor
24	R-61820GRPL	618/620 Gripple

R-H503WAYGUY — H50
Actual Wire Required - 1000′

1	R-618	1000′ - 6 Strand/18 GA Wire
3	R-GAS4303	3′ x 1/2″ Screw Anchor
30	R-61820GRPL	618/620 Gripple

4-Way Guy Kits

R-H204WAYGUY — H20
Actual Wire Required - 250′

1	R-618	1000′ - 6 Strand/18 GA Wire
4	R-GAS4303	3′ x 1/2″ Screw Anchor
16	R-61820GRPL	618/620 Gripple

R-H304WAYGUY — H30
Actual Wire Required - 500′

1	R-618	1000′ - 6 Strand/18 GA Wire
4	R-GAS4303	3′ x 1/2″ Screw Anchor
24	R-61820GRPL	618/620 Gripple

R-H404WAYGUY — H40
Actual Wire Required - 800′

1	R-618	1000′ - 6 Strand/18 GA Wire
4	R-GAS4303	3′ x 1/2″ Screw Anchor
32	R-61820GRPL	618/620 Gripple

R-H504WAYGUY — H50
Actual Wire Required - 1200′

2	R-618	1000′ - 6 Strand/18 GA Wire
4	R-GAS4303	3′ x 1/2″ Screw Anchor
40	R-61820GRPL	618/620 Gripple

Additional Accessories Available

Universal Ridge Mounts
R-UM20
R-UM30
R-UM40
R-UM50

Universal Ridge Mount
R-ETMB

Ground Mounts
R-GTMBL